

HydroForce HF-250 PRO Documentation

Industrial Engineering

SLP | Modapts | Lean

Project Status: Completed

Project Overview

This document serves as the comprehensive engineering README and technical specification manual for the end-to-end product industrialization framework, commercial feasibility models, process workflow architectures, and manufacturing facility layout designs for **HydroForce Industries (Pty) Ltd**, based in Epping Industrial, Cape Town.

The primary objective of this enterprise is the local manufacturing and assembly of the **HydroForce HF-250 PRO**—a heavy-duty, SANS-compliant 250 Bar electric pressure washer designed to serve as an agile, cost-effective alternative to premium imported European brands. The engineering framework bridges macroeconomic market strategy with micro-level shop floor workstation ergonomics, systematically structured across the evaluation rubrics of Course **FAM360S**.

Repository Structure

└─ Phase-1_Product-Industrialization/	# FAM360S Submission 1 Deliverables
└─ Financial-Models/	# Setup Costs, Breakeven, & 5-Year P&L Excel Engines
└─ CAD-Assemblies/	# SolidWorks Exploded Views & Component Drawings
└─ Sourcing/	# Bill of Materials (BOM) & Make-or-Buy Matrix
└─ Phase-2_Process-Engineering/	# FAM360S Submission 2 Deliverables
└─ Routings/	# Detailed Production Routing Spreadsheets
└─ Process-Maps/	# OPC, FPC, and Assembly Charts
└─ Flow-Evaluation/	# Master Flow Patterns & Multi-Criteria Matrix
└─ Phase-3_Facility-Layout-Design/	# FAM360S Final Submission Deliverables
└─ Workplace-Ergonomics/	# Workstation Footprints & Modapts Standards
└─ Operations/	# Mathematical Assembly Line Balancing Models
└─ Master-Layout/	# AutoCAD/Visio Factory Master Blueprint (2D/3D)

Technical Product Specifications

The flagship HF-250 PRO is engineered for continuous commercial deployment across construction, agriculture, food logistics, and mining sectors.

Technical Feature	Specification
Pressure Rating	250 Bar (3,626 PSI) — fully adjustable from 50–250 Bar
Flow Rate	15 L/min (rated) max 21 L/min
Power Source	Electric (7.5 kW / 400V 3-phase motor)
Pump Type	Triplex ceramic plunger pump with stainless steel manifold
Chassis Frame	Heavy-duty, powder-coated steel chassis with compact trolley
Mobility	Heavy-duty swivel caster wheels
Compliance	SANS/IEC compliant; NRCS letter of authority applied

Engineering Execution Phases

Phase 1: Product Industrialization & Financial Feasibility

1. Capital Requirements & Initial Investment: The startup framework details a total initial setup investment of **R2,500,000**, featuring R360,000 for a 500 m² factory advance lease, R180,000 for facility fit-out, R450,000 for assembly tooling, and R620,000 for initial build-up component inventory stock.

2. Breakeven & Contribution Analysis: With an Average Selling Price (ASP) of R20,500 per unit and a Variable COGS of R12,700 per unit, the Contribution Margin is established at R7,800 per unit. Balanced against annual fixed operating costs of R1,440,000, the mathematical breakeven point is determined at **~185 units / year**, yielding a payback period of ~3.6 years and a 218% 5-year ROI.

[Average Selling Price: R20,500] → Minus COGS: R12,700 → [Contribution Margin: R7,800]

Breakeven Volume = Fixed Costs (R1,440,000) ÷ R7,800 = 185 Units / Year

3. Bill of Materials (BOM) & Strategic Sourcing Decisions: A complete parts breakdown determines internal assembly routing vs parts outsourcing:

Part No.	Part Name	Qty	Strategy
1	Base Plate	1	MAKE (AISI 4130 Steel)
2	Nozzle Bar Frame	2	MAKE (316 Stainless Steel)
3	Elbow Pipe	6	MAKE (AISI 347 Stainless)
7	AC Motor	1	BUY (7.5 kW 3-Phase)
8	High Pressure Pump	1	BUY (Triplex Ceramic)
13	Flat Spray Nozzle	16	MAKE (PVDF)
14	Spartan Caster Wheel	4	BUY (N/A)

Phase 2: Process Engineering & Macro-Flow Synthesis

- **Production Style Selection:** Implemented a hybrid cellular assembly line and fixed-position layout optimized for batch manufacturing to achieve the targeted production volume growth.
- **Process Mapping:** Generated comprehensive Operation Process Charts (OPC) and Assembly Charts capturing the exact chronological sequence of operations and inspections.
- **Method Study & Logistics Optimization:** Engineered Flow Process Charts (FPC) documenting transport distances and structural delays. Evaluated two alternative Master Flow Patterns using a multi-criteria weighted evaluation matrix scoring safety, material handling effort, and backtracking avoidance.

Phase 3: Facility Layout Construction & Work Design

- **Systematic Layout Planning (SLP):** Developed Activity Relationship Charts (ARC) and proximity worksheets to logically arrange production zones relative to auxiliary services (Toolroom, Testing, Offices, and Ablutions).
- **Work Study & Ergonomics:** Designed custom manual assembly workstations using Modapts Standards to calculate baseline standard times, reduce industrial fatigue, and maximize line efficiency.
- **Layout Optimization & Assembly Line Balancing:** Applied balancing algorithms to minimize idle times and eliminate work-in-progress (WIP) accumulation. Formulated strict dimensioned footprint parameters for logistics nodes (Receiving, Warehousing, Shipping) to produce the final 2D blueprint layout.

Projected Business Impact (5-Year Forecast)

- **Year 1 (2026):** 220 Units Sold | R4,510,000 Revenue | R255,000 Net Profit
- **Year 5 (2030):** 324 Units Sold | R6,642,000 Revenue | R1,152,000 Net Profit
- **5-Year Cumulative Impact:** 1,340 units sold generating R27,470,000 total revenue at an 8% steady compound growth trend.

Author: Fadeel Phillips

Institution: Cape Peninsula University of Technology (CPUT)

Department: Industrial & Systems Engineering

Course Code: FAM360S

Document Version: 1.0 (PDF README)